

Open Automated Demand Response Communications in Demand Response for Wholesale Ancillary Services

Sila Kiliccote, Mary Ann Piette, Girish Ghatikar

Lawrence Berkeley National Laboratory

Ed Koch, Dan Hennage

Akuacom

John Hernandez, Albert Chiu, Osman Sezgen

Pacific Gas and Electric Company

John Goodin

California Independent System Operator

November 18, 2009

Sponsored by California Energy Commission

Demand Response Research Center





Presentation Overview

- Objectives
- System Architecture
- Methodology
- Results
- Conclusion and Next Steps



Participating Load Pilot Project

Research Objectives:


- Can OpenADR be used for ancillary services?
- Are current DR strategies in C&I fast enough for fast DR?
- Can the communication infrastructure over the Internet accommodate fast DR requirements: PL Resources have to meet non-spinning reserve requirements:
 - the resources have to deliver energy within 10-minutes,
 - be available for 2 hours, and
 - provide real-time telemetry to the CAISO

•PLP Team:

- PG&E
- Itron
- Akuacom
- CAISO
- Metrum Technologies
- Bow Networks
- LBNL



Participating Load Pilot (PLP) Architecture



Acronyms:

EMS – Energy Management System

ADS – Automatic Dispatch System

SIBR – Scheduling Infrastructure Business Rules

DRAS – DR Automation Server

CLIR – Client Logic with Integrated Relay

RM – Revenue Meter

T – Telemetry



Methodology

- Site Selection: Developing criteria that considers load variability, weather sensitivity and load statistical summaries
- DR Strategies: Each facility used their existing DR strategies. One facility test the use of feedback.
- Ramp Rate Calculations: (MW/min)
- Data collection: 15 min, 5 min and 4 sec. data
- Demand Shed Calculations: Forecasted loads are considered baseline.
- Settlement Calculations: (Actual Meter DayAhead Schedule) X Real-Time Price
- Dispatch Signal Propagation: Dispatch received in XML




DR Strategies

Site	DR Strategy	DR Period	
IKEAEPA	Turning off 11 RTUs out of 43 and raising zone setpoints to 76 DegF	Noon to 6 pm	
Contra	4 DegF Global Temperature		
Costa	Adjustment with 1 DegF	2 pm to 6 pm	
County	increments	_	
Svenhards	Turn off Pan Washer	3 pm to 5 pm	




OpenADR Signals – Critical Peak Pricing (CPP)





OpenADR signals - PLP





Test Dates and Sample Results


Site/Date	17-Jul	6-Aug	27-Aug	31-Aug	11-Sep	18-Sep	21-Sep	22-Sep
						16:00 - 16:25,		
IKEA EPA	15:00 - 17:00				14:40 - 14:43	16:35 - 16:50		
						16:00 - 16:25,	14:00 - 16:30,	
CCC	15:00 - 17:00	17:00 - 18:00		14:00 - 15:00	14:40 - 14:43	16:35 - 16:50	16:40 - 17:55	
						16:00 - 16:25,		
Svenhards	15:00 - 17:00	15:00 - 16:00	15: 25 - 15:30			16:35 - 16:50	16:30 - 16:40	16:55 - 17:00

		vs. Actual	Forecasted vs. Actual Average Load Reduction				
Site	Date	Ramp Rate (MW/min)	HE 15:00	HE 16:00	HE 17:00	HE 18:00	
Office	21-Sep	0.002/0.006	20/72	80/86	40/51	30/49	
Bakery	18-Sep	0.012/0.012	-	-	120/143	-	
Retail	18-Sep	0.001/0.01	_	-	50/20	-	



Contra Costa County – Office Building





Forecasted - Actual -

- Hourly Forecasted Bids



Conclusion

- HVAC as an end use and global temperature adjustment as a DR strategy meet the requirements for wholesale ancillary services.
- OpenADR specification is used to communicate wholesale DR events in an open and interoperable way.
 - Customer's transition from Auto-DR programs to PLP is seamless
- Internet can be used for fast DR to dispatch nonspinning ancillary services.



Next Steps

- Need to resolve glitches....
 - Dispatch rules were assumed to be sorted at the CAISO system and little intelligence was programmed into the DRAS in terms of program rules.
 DRAS can be used as a second check point for dispatch rules.
 - Maximum duration of dispatch and number of events for the PLP sites is not sufficient to test sustainability of sheds.
- Forecasting loads is a complex process and highly variable loads are extremely difficult to forecast. There is a need to develop better forecasting methods where load characteristics and changing in loads are better incorporated in the forecasting algorithms.
- Cost of telemetry for each site needs to be analyzed and scalability issues need to be explored.
- Settlements were not completed by the time this paper was written. Various value streams should be investigated.



Thank you!

Sila Kiliccote

skiliccote@lbl.gov

http://drrc.lbl.gov



Automation Goals and Definition

- -Recent Research Goals
- Cost Develop low-cost, automation infrastructure to improve DR capability in California
- Technology Evaluate "readiness" of commercial buildings to receive signals
- Capability Evaluate capability of control strategies for current and future buildings
- -Auto-DR Definition Fully automated signals for end-use control
- Signaling Continuous, secure, reliable, 2-way comms; listen and acknowledge
- Industry Standards Open, interoperable communications to integrate with both common EMCS and other end-use devices that can receive a relay or similar signals (such XML)
- Timing of Notification Day ahead and day of signals facilitate diverse strategies



Interview site after each event


Auto-DR Multi-Year Technology Development Summary

□ Develop Demand Response Automation Server (annually updated)
 □ Develop connection to Energy Management Control Systems (EMCS)
 □ Field Tests – Recruit sites/ 2 to 12 events per summer
 2003 - 5 sites – Internet link to Energy Information Systems (EIS)
 2004 - 18 sites - linked to EIS and EMCS
 2005 - PG&E CPP collaboration
 2006 - PG&E, SDG&E, Planning with SCE
 2007 - PG&E and SCE
 2008 - PG&E and SCE
 2009 - Bonneville Power Administration/ Seattle City Light, Participating Load Pilot w/ PG&E
 □ Evaluate with weather normalized baseline

Year	# of Sites	DRAS	Site Communications	Utility
2003	5	Infotility	XML Gateway Software	None
2004	18	Infotility	XML - Internet Relay	None
2005	11	Akuacom	XML - Internet Relay	PG&E
2006	25	Akuacom	XML - CLIR	PG&E, SDG&E
2007-08	200+	Akuacom	XML - CLIR	Statewide




Site Selection







Schedule Submission Process





IKEA - Retail





Forecasted-Actual — Hourly Bid



Svenhard's Swedish Bakery

